BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Name of Work: Improvements and Asphalting 10th Cross (between 8th main and Pipe line Road) Bhuvaneshwarinagara in Bagalagunte Ward No.14, T.Dasarahalli Sub Division.

			Est. Cost Rs.				20.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1.	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)								
	10th Cross	Cum	1	410.00	5.00	0.30	615.00		
							615.00	86.92	53456.00
	Basic Rate	82.00							
	Add Area Weightage 6%	4.92							
	Total	**86.92**							
2	KSRRB M400-1 For Grading I material construction of **granular sub-base** by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material .Page No 155/ Item No. 20.6.1 PWD SR 2016-17								
	10th Cross	Cum	1	410.00	5.00	0.10	205.00		
	Basic Rate	1433.00					**205.00**	1518.98	311391.00
	Add Area Weightage 6%	85.98							
	TOTAL	**1518.98**							
3	Providing, laying, spreading and compacting graded stone aggregates to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.								
	10th Cross	Cum.	1	410.00	5.00	0.23	471.50		
	Basic Rate	1668.00					471.50	1768.08	833650.00

	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
	Add Area Weightage 6%	100.08							
	Total	1768.08							
4	Providing and applying **primer coat** with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWDSR 2016-17, P.No.161, I No.21.6)								
	10th Cross	Sqm	1	410.00	5.00		2050.00		
							2050.00	27.56	56498.00
	Basic Rate	26.00							
	Add Area Weightage 6%	1.56							
	Total	27.56							
5	Providing and laying **bituminous concrete** with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen(p-164, lt 21.22.6) PWD SR 2016-17								
	10th Cross	Cum	1	410.00	5.00	0.045	92.25		
	Basic Rate	6859.00					92.25	7270.54	670707.00
	Add Area Weightage 6%	411.54							
	Total	7270.54							
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. ~~2.00~~ 2.50 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17								
		Cum	Qty Vide Item No. 1				615.00	~~85.65~~	52674.00
	Loading and	68.00						80.80	49692.00
	Lead 4 KMs	12.80	[2.5×1.28×4]						
		80.80							
	Add Area Weightage 6%	~~4.85~~							
	Total	~~85.65~~							

	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
	Quality control Test Charges 1%								20000.00
8	Miscellaneous and UnforessenCharges								1624.00
									4606
								Total	2000000.00
	(Rupees Twenty Lakhs Only)								

CERTIFICATE:-

1. The Work spot has been inspected and the work is found to be necessary
2. The Estimate is prepared as per the PW,P & IWTD -SR-2016-17
3. The Provision made in estimate are adequate and essential.
4. This area comes under BBMP limits.

Assistant Engineer
Bagalagunte Ward 14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ. CE/DZ/AS/56/16-17 ದಿನಾಂಕ : 09/01/2017
ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷಗಳು ಮಾತ್ರ/-
Rs. Twenty lakhs only/- ಗಳ
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/85/16-17 ದಿನಾಂಕ : 10.01.17
ರೂ. Twenty lakhs only
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾತ್ಕಾಲಿಕ ಮಂಜೂರಾತಿ ನೀ...
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Name of work:- Improvements & ~~Asphalting~~ to 10th Cross (Between 8th main & ~~[illegible]~~ & Pipeline road) Bhuvaneshwari Nagara in Bangalagutte W No. 164.

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಸವೇಶ್ವರ ವಲಯ-ಪೂರ್ವ
ಬಾಗಲಗುಂಟೆ, ಬಿಬಿಎಂಪಿ
ಬೆಂಗಳೂರು